
UPRIGHT FRAMELESS PEDESTAL ASSEMBLY AND IN GROUND INSTALLATION



PARTS

- A Sign (×1)
- B Sign posts with welded flange (×2)

TOOLS REQUIRED

5/32" Allen driver

Post hole digger

Shovel

Level

Tape Measure

Tamping stick for gravel

Kraft paper or plastic sheet

Wood braces and clamps

MATERIALS NEEDED

Concrete and/or class 5 gravel 6-8" length of rebar (if desired)

ASSEMBLY DIRECTIONS

- Unpack all parts and inspect for damaged or missing items.
- 2. Arrange all items for assembly using corrugated packaging to protect items from damage.
- With two people, attach the sign panel to the flange welded to the post using hardware provided with the high pressure laminate sign. DO NOT OVERTIGHTEN.
- Insert rebar through hole on post ends (if desired) to form a "T". Dig 8"-10" diameter holes 6" below the frostline, spaced 4"-5" wider than the width of the sign.

- Add several inches of tamped gravel to serve as footing base. Verify installation height—bottom of sign should mount 28'-32" from grade.
- 6. Wrap posts with kraft paper or plastic sheet to protect from concrete spatter. Stabilize posts in holes with wood braces and clamps. Backfill with additional tamped class 5 and/or prepared concrete.
- After concrete has set (if used), remove braces and plastic sheeting, if used.

